BANGALORE DIVISION.

Notification dated 16th—22nd August 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 7th September 1929, for constructing a Primary School Building at Settihalli, Channapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3. (*a*) Tenders quoting percentages above or below the sanctioned estimate will not be accepted.

4. Each tender must be accompanied by a deposit of rupees one hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Primary School Building at Settihalli, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of the quantities for the Primary School at Settihalli, Channapatna Taluk.

No.	Items of work	Quantity	Unit	Rate
				Rs.
1	Earthwork excavation and foundation and filling in basement level.	41	C.yd.	
2	Burnt stone jelly concrete in mortar	263	C.ft.	
3	Burnt stone in clay, foundation and basement ...	1,374	,,	
4	Burnt brick in clay, Superstructure	1,754	,,	
5	Burnt brick in mortar, Superstructure	316	,,	
6	Burnt stone slabs 6″ thick roughly dressed	208	S.ft.	
7	Teak wood doors with battened shutters 1¼″ thick planks with iron fittings, etc., complete.	46	,,	
8	Teak wood windows with battened shutters 1″ thick planks, 5/8″ dia. iron bars and iron fittings, etc., complete.	63	,,	
9	Teak wood gate with double shutters and iron fittings, etc., complete.	20	,,	
10	Teak wood wicket gate with iron fittings, etc. ...	36	,,	
11	Honney wood work wrought and put up	117·35	C.ft.	
12	Roofing with First Class Mangalore Tiles on 1″ x 2″ teak reepers.	19·06	Sqr.	
13	Ridge tiles set in mortar	168	R.ft.	
14	Plastering with mortar	45·00	Sqr.	
15	White and colour washing	45·00	,,	
16	Flooring with 3″ thick granite stone slabs on 6″ sand bed and cement pointing.	10·20	,,	
17	Tarring to wood work, three coats	5·00	,,	
18	Chacolate painting, three coats	6·00	,,	
19	Teak wood eve board	238	R.ft.	
20	Pointing with mortar	4·00	Sqr.	
21	Masonry finials and cornice work to gate pillars, etc., complete	2	Each	
22	Coping over compound wall	54	R.ft.	